

Baseline Survey of Alternative In-Line Inspection Vehicles

DOT Agreement No. DTRS56-02-T-0004

SwRI Project 14.06170

Status Review Meeting
October 7, 2003
Southwest Research Institute
San Antonio, TX

Why Pipeline Inspection?



Project Description

- Relates to in-line inspection (ILI) of piggable and unpiggable pipelines
- Contract signed 1 October 2002
- Project term 9 months (extended to 12 mo.)
- Pipeline Research Council, International is co-funder.
- Total project cost is \$ 80,000.

Project Goals

- Document scope of problem of unpiggable pipelines
- Document state of the art in ILI capabilities
- Determine tool capability in other applications
- Document conceptual designs including tethered and autonomous robotic vehicles
- Produce comprehensive report of findings

Unpiggable Pipelines

- Restrictive pipe diameters (telescoped lines)
- Restrictive valves (undersized, non-full-opening, plug valves)
- Restrictive bends (Short radius, mitered, heavy wall, back-to-back)
- Low pressure lines
- Low flow-rate lines
- Lack of access (no traps installed)

Bend with Smaller Valve




Tee Branch Connection



Reduced Tee Branch




Plug Valve Construction




View Looking into Plug Valve




Measurement / Sensors for In-Line Inspection




Measurement / Sensors for In-Line Inspection




Measurement / Sensors for In-Line Inspection







Measurement / Sensors for In-Line Inspection




Measurement / Sensors for In-Line Inspection




MFL Smart Pigs





MFL Operating Principle



UT Operating Principle



Ultrasonic Smart Pigs



ILI Providers

- BJ Process and Pipeline Services
- Baker Petrolite Corporation
- A. Hak Industrial Services
- NDT Systems and Services
- 3P Services GmbH
- PII Pipeline Solutions (GE Power Systems)
- Rosen Inspection
- Tuboscope Varco

Pig Matrix Parameters

Pipe Size	NDE Technique
Number of Modules	Bend Radius
Minimum Op. Pressure	Max Op. Pressure
Max Wall Thickness	Tween Distance
Minbore Continuous	Minbore Delta
Pig Length	
Maximum Unbarred Branch Diameter	

Alternative Applications

- Viewing devices (TV crawlers)
- Internal piping repair systems (tethered)
- Sewer inspections, repairs
- Water main inspection (Remote Field EC)
- General robotic devices (surveillance, hazardous environment, mine detection/disposal)

Alternative Concepts

- Caterpillar-track robot
- Articulated linear segment crawler (NYGAS Explorer)
- “Bicycle chain” configurable device (Sandia)
- Inch-worm drive – Push-pull (CTS)
- Robotic snakes



SRI International Pipeline Robot





Pipeline Robot

We designed and developed the Magnetically Attached General Purpose Inspection Engine (MAGPIE) to inspect small (15 cm) natural-gas pipes for corrosion and leakage. The robot's magnetic wheels enable it to travel on the ceiling and sides of pipes, and to navigate obstacles such as T-joints, vertical climbs, and sleeve joints. A demonstration robot, with on-board battery power, has been successfully tested; it sends control signals and pipeline video images through a fiber-optic cable.


Wheeled/Tracked Crawlers



Wheeled Robots in Piping



Devices from other Applications



Robotic Welding






Sealant
Application






Makro

Snake Robots




Snake Robots




Carnegie Mellon Snakes



Carnegie Mellon Robots



Carnegie Mellon Pipe Robot



Dr. Gavin Miller's Snake (S5)



Dr. Miller's Fifth Attempt



Current Status

- Draft report submitted 8/31/03
- Final version awaiting comments from draft review

Feasibility of In-Line Stress Measurement by Continuous Barkhausen Method

DOT Agreement No. DTRS56-02-T-0003

SwRI Project 14.06172

Status Review Meeting

October 7, 2003

Southwest Research Institute

San Antonio, TX

Project Description

- Relates to in-line inspection (ILI) for stress zones such as hard spots or mechanical damage
- Relates to magnetic flux leakage (MFL) inspection
- Contract signed 1 October 2002
- Project term 18 months (extended to 24 mo.)
- H. Rosen Engineering GmbH is co-funder and co-investigator.
- Total project cost is \$ 160,000.


Project Goals

- Determine feasibility of implementing Continuous Barkhausen Noise (CBN) measurement on MFL smart pig.
- Determine optimum sensor design
- Determine optimum sensor location
- H. Rosen performs pull tests and field tests
- Produce comprehensive report of findings


Properties of CBN System

- Takes advantage of earlier in-house work at SwRI
- Takes advantage of MFL pig magnetic field
- Simple sensor and circuitry
- Could expand capabilities of MFL ILI with minimal hardware addition
- Potentially more robust than competing ways of detecting stress anomalies


Conventional Barkhausen Circuit



Continuous Barkhausen Arrangement



MFL Pig Magnetic Circuit



Current Status

- Rosen supplied magnetic field distributions around typical MFL pig
- Modeling was performed to suggest sensor placement
- Laboratory tests were performed to validate the technology
- Sensors and electronics were designed and fabricated to support pull testing.

Current Status (cont'd)

- Pull testing performed at Rosen facility in Houston validated effectiveness of sensor on MFL pig in detection of stress anomalies

Laboratory Set-Up




Barkhausen Sensor



Peened Defect made with Pneumatic Scaler



Laboratory Continuous Barkhausen Apparatus



Pull Testing at Rosen

- Two specimens with multiple manufactured defects were provided by SwRI
- Specimens were assembled with other Rosen pipe to make 25m test section
- CBN sensors and electronics attached to Rosen MFL pig
- Multiple runs made at different speeds

One Specimen for Pull Tests




Peened ID Defect



Quenched OD Defect



Interface Circuits



Barkhausen Pull-Test Line

17-Jul-03

Pipe measurement reference is at 12:00 (0 degrees) at the start end of the pipe, with angle CW in direction of travel.

Pipe No. 1: Diameter = 16 inches, Wall Thickness = 0.375" (9.5 mm) Inlet tray.

Axial Location Distance from launch (m)	Angular Position (Degrees)	Size	Item
0.00	N/A		Start of Pipe
1.52	0		End of launch tray
4.65	N/A		Pipe girth weld

Pipe No. 2: Diameter = 16 inches, Wall Thickness = 0.188" (4.8 mm)

Axial Location Distance from launch (m)	Angular Position (Degrees)	Size	Item
4.65	N/A		Pipe girth weld
6.49	0	1" dia.	Grind marks
6.49	0, 270		OD sensors
7.70	N/A		Pipe girth weld

Pipe No. 3: Diameter = 16 inches, WT = 0.375 inches (9.5 mm) Grade X-52 Welded

Axial Location Distance from launch (m)	Angular Position (Degrees)	Size	Item
7.70	N/A		Pipe girth weld
8.17	90	1" dia.	Drilled Hole
9.08	180	7" dia.	Hole with Coupon
9.08	0	2" ax. 10" circ.	Defect P1 - Peened Area on ID Surface
9.71	90	3" dia.	Defect P3 - Peened Area on OD Surface
10.30	180	7" dia.	Hole with Coupon
10.30	0	2" ax. 10" circ.	Defect Q1 - Quenched Area on ID Surface
10.37	0, 270	N/A	OD Sensors
11.52	180	7" dia.	Hole with Coupon
11.52	0	2" ax. 10" circ.	Defect P2 - Peened Area on ID Surface
12.15	90	3" dia.	Defect Q3 - Quenched Area on OD Surface
12.74	180	7" dia.	Hole with Coupon
12.74	0	2" ax. 10" circ.	Defect Q2 - Quenched Area on ID Surface
13.66	90	1" dia.	Drilled Hole
14.13	N/A		Pipe girth weld

Pipe No. 4: Diameter = 16 inches, WT = 0.188 inches (4.8 mm) Grade X-52 Welded

Axial Location Distance from launch (m)	Angular Position (Degrees)	Size	Item
14.13	N/A		Start of Pipe
14.45	180	1" dia.	Drilled Hole
15.36	180	7" dia.	Hole with Coupon
15.36	0	2" ax. 10" circ.	Defect P1 - Peened Area on ID Surface
15.96	90	3" dia.	Defect P3 - Peened Area on OD Surface
16.58	180	7" dia.	Hole with Coupon
16.58	0	2" ax. 10" circ.	Defect Q1 - Quenched Area on ID Surface
17.80	180	7" dia.	Hole with Coupon
17.80	0	2" ax. 10" circ.	Defect P2 - Peened Area on ID Surface
18.41	90	3" dia.	Defect Q3 - Quenched Area on OD Surface
19.01	180	7" dia.	Hole with Coupon
19.01	0	2" ax. 10" circ.	Defect Q2 - Quenched Area on ID Surface
19.91	0	2" ax. 10" circ.	ID Quench Defect - New
19.93	180	1" dia.	Drilled Hole
20.25	N/A		End of Pipe

Pipe No. 5: Diameter = 16 inches, Wall Thickness = 0.375" (9.5 mm). Receiver tray

Axial Location Distance from launch (m)	Angular Position (Degrees)	Size	Item
20.25	N/A		Pipe girth weld
21.19	0	2" ax. 10" circ.	ID Quench defect - New
22.53	0	2" ax. 10" circ.	ID Quench defect - New
23.22	N/A		Receive tray
24.74	N/A		End of Pipe


Pull-Rig Set-Up at Rosen Houston




Data Acquisition and Storage



Barkhausen sensor attached to MFL pig magnetic pole piece





Rosen MFL pig in launch tray





Pulling equipment and receiver tray



Sensor and interface circuit




Raw Barkhausen signals from heavy wall and light wall pipes



Processed data from two test specimens

Run 008 - 7-09-03

Difference Signal



Status and Plans

- Analysis of data from pull tests continuing.
- Discussions are under way with Rosen on potential for field test